

825EQ

Alyward #4 Stratman,
NW NE SE, 1-17S-10W.
Elevation 1793'

Pennsylvanian conglomerate. 3216-3240'

3216-3221 Shale, green, with thin layers of red.
3221-3236 Lime, pink; tends to be nodular. Rare red clay.
3236-3240 Sand, fine, medium, and coarse.

Ordovician Top 3240' Sub-sea, minus 1447'

Decorah 3240-3254'

3240-3251 Shale, green and maroon; with sandy layers.

3251-3254 Sand, fine, cemented. Oilstained. Pipe lowered to 3253'.

Arbuckle 3254-3261 Penetration 7'. Sub-sea, minus 1461'.

3254-3261 Miller, probably zone 9. Penetration not sufficient
to get a reliable zone contact. Oil rose 500' from
3254-3256'. At 3261' swabbed 90 bbls. per hr.

Sub-sea on Purcell, zone 5, cannot be estimated closer than 25'.
The point cannot be above minus 1487' and probably not below minus
1515'.

Correlated from general information from wells in 1-17S-10W.