

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

508 East Murdock, Wichita, Kansas


11-17-11W

Company - THE ELDORADO REFINING COMPANY
 Farm - Ehler "A" No. 10

SEC. 11 T. 17 R. 11W
 SE NW SE

Total Depth. 3370
 Comm. 4-11-50 Comp. 5-9-50
 Shot or Treated.
 Contractor. Sterling Drlg. Co.
 Issued. 5-27-50

County. Barton
 KANSAS



CASING:

8 5/8" 320' cem w/160 sx.
 5 1/2" 3356' cem w/160 sx.

Elevation. 1918 2nd.

Production. Pot. 402 bbls.

Figures Indicate Bottom of Formations.

surface clay, shale	
and shells	280
shale, shells	325
shale	375
shale, shells, redbed	700
anhydrite	725
shale, shells	975
shale, shell, salt	1400
lime, shale	1445
lime	1630
lime, shale	1865
lime	2175
lime, shale	2300
shale	2425
lime shale	2690
lime	2830
lime, shale	2905
lime	2960
lime, shale	3060
lime	3356
arbuckle RTD	3360
lime Arbuckle	3370
Total depth	

Tops: D.F.

Heebner	2955
Brown Lansing	3055
Lansing	3068
Conglomerate	3349
Arbuckle	3355

D.P. & D.D. 3362, S.F.O.

DD 3368, 1200' FU/12 hrs.

DD 3370 T.D. \$ 10 BOPH, \$100 BO/4 hrs.