

11-17-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock, Wichita, Kansas

Company - THE ELDORADO REFINING CO.  
Farm - Ehler "A" No. 13

SEC. 11 T. 17 R. 11W  
SE SE SE

Total Depth. 3335  
Comm. 5-11-50 Comp. 5-22-50  
Shot or Treated.  
Contractor. Sterling Drlg. Co.  
Issued. 9-2-50

County. Barton  
KANSAS



CASING:  
8 5/8" 320' cem w/150 sx.  
5 1/2" OD 3333' cem w/75 sx.

Elevation. 1895 DF

Production. 455 BO, no water.

Figures Indicate Bottom of Formations.

surface clay, shale	160
sand	180
shale, shells	675
anhyd.	705
shale, shells, salt	1200
lime, shale	1660
lime	2125
lime, shale	2730
lime	2910
lime, shale	3030
lime	3305
lime, shale	3320
lime arb. RTD	3325
lime	3335
Total depth	

Tops: DF	
Heebner	2925
Br. lime	3034
Lansing	3047
Arbuckle	3317
no cong.	

DST 3142-49, op 1/2 hr, rec. 25' thin mud  
w/trace oil, BHP 600#.  
DST 3202-10, op. 1 hr. rec. 100' muddy salt  
water, BHP 810#.  
Light odor, fair show free oil, 3317:19  
D.P. and DD to 3335 T.D. good pay 3333-35,  
§ 13 BOPH /3 hrs.