

11-17-11 W

WELL LOG BUREAU · KANSAS GEOLOGICAL SOCIETY


508 East Murdock, Wichita, Kansas

Company - THE ELDORADO REFINING CO.
 Farm - Ehler "A" No. 15

SEC. 11 T. 17 R. 11W
 SE NE SE

Total Depth. 3384
 Comm. 6-4-50 Comp. 6-13-50
 Shot or Treated.
 Contractor. Sterling Drlg. Co.
 Issued. 6-8-50

County. Barton
 KANSAS



CASING:
 8 5/8" 320' cem w/150 sx.

Elevation. 1906.52

Production. dry

Figures Indicate Bottom of Formations.

surface soil, clay	40
shale, shells	100
shale, shells, sand	320
shale, sand	685
anhydrite	705
shale, shells	820
shale, shells, salt	1350
lime, shale	1660
lime	2075
lime, shale	2695
lime	2925
lime, shale	3045
lime	3335
conglomerate	3347
conglomerate, lime and shale	3371
ar buckle	3384
Total depth	

Tops: D.F.	
Heebner	2938
Br. lansing	3044
Lansing	3059
Conglomerate	3336
Ar buckle	3368

Tried take DST 3 times, packer failed.