

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bk Bldg., Wichita, Kansas.

N-17-11W  
Plotted  
B. Hopman

THE CARTER OIL CO.  
Dennis Hogan No. 1.


SEC. 11 T. 17 R. 11W  
NE SW NW  
990' fr S & 330 fr E.L.

Total Depth. 3336  
Comm. 9-24-37 Comp. 10-18-37  
Shot or Treated.  
Contractor, Parker Drilg. Co.  
Issued, 11-13-37

NOV 13 1937

County. Barton.

Rotary



CASING.

10" 209'  
7" 3325'

Elevation.

Production. Pot. 1890 B.

Figures Indicate Bottom of Formations.

cellar	10
surface clay	30
shale	100
shale shells	180
sand	195
sand shale shells	215
shale shells	565
red bed	660
shale shells	696
anhydrite	737
shale shells	1150
salt and shale	1275
salt	1370
lime shale	1485
shale broken lime	1715
shale and lime	1749
sand sharp	1765
shale broken lime	1825
sticky shale	1925
shale broken lime	2019
shale lime	2071
broken lime and shale	2145
shale shells	2235
shale lime	2333
shale shells	2415
shale broken lime	2472
shale lime	2535
shale shells	2600
broken lime shale	2635
shale shells	2650
lime	2745
shale streaks lime	2810
lime	3075
shale	3083
lime	3120
lime shale	3132
cored shale lime	3145
slight oil stain at 3143.	
lime	3225
cored lime	3243
lime	3300

cored lime	3313
lime	3331
cored lime	3336
Total Depth.	

Top of Douglas 2980  
Kansas City Lansing Top 3060  
small show oil 3326-31 Top siliceous 3326  
good show oil 3331-36