

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

888


11-17-11W

CARTER OIL CO.
D.Hogan No. 4.

SEC.11 T. 17 R.11W
CEL NW NW

Total Depth. 3345'
Comm. 7-9-41 Comp. 7-24-41
Shot or Treated.
Contractor. Iron Drlg.Co.
Issued. 9-6-41

County. Barton



CASING:
8 5/8" 241'
5 1/2" 3337'

Elevation.

Production. ~~Pet. 212 B.~~
2113 bbls oil &
642 BW (cum)

Figures Indicate Bottom of Formations.

post rock & clay 185
sand 210
shale & shells 245
red rock & shale 379
shale & shells 485
red rock & shells 716
anhydrite 738
shale & shells 1180
salt 1275
shale & shells 1334
lime & shale 1404
anhydrite & shale 1508
shale & lime 1549
shale & lime 1685
lime & sdy shale 1793
shale shells strks
pyrite 1850
shale & lime 1890
shale 1920
shale & lime 1994
shale 2004
shale & lime 2110
shale & shells 2223
shale, red bed, lime 2406
lime 2428
shale & lime 2526
lime 2550
lime brkn 2584
shale & lime 2679
shale 2710
shale & lime 2754
lime brkn 2778
cherty lime 2786
lime brown 2813
shale & lime 2822
chert & lime 2826
shale & lime 2847
lime 2877
lime 2906
brkn chert, shale
& lime 2918
lime 2923
shale & lime 3055

Tops: Topeka 2710
Douglas 2970
K. C. lime 3069
Arbuckle 3336
sm sh oil 3073-78
good porosity & very
slight sh oil 3164-85
slight sh oil 3241-44

lime 3068
shale & lime 3093
lime 3216
shale & lime 3261
lime 3327
shale 3339
lime 3345
Total Depth.

