


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HOME STAKE OIL CO.
Farm- Zorn No. 1

SEC. 6 T. 17 R.11W
SW SE NW

Total Depth. 3315'
Comm. 12-16-57 Comp. 12-28-57
Shot or Treated.
Contractor. Sierra Petroleum Co.
Issued. 6-21-58

County Barton
KANSAS



CASING:

8 5/8" 500' cem w/300 sx.
5 1/2" 3302' cem w/100 sx.

Elevation. 1856' DF

Production. 10 BOPD

Figures indicate Bottom of Formations.

shale & shells	395
sand hard & shale	490
shale & shells	500
red bed	710
Anhydrite	745
shale & shells	950
shale & salt	1115
shale & shells	1730
lime & shale	2731
lime	2848
lime & shale	2899
lime	2954
lime & shale	3055
lime	3233
lime & shale	3304
lime	3315
Total Depth	

DST #3 3297-3307, op 45 mins, weak blow which died
in 7 mins. Bypassed tool at 15 mins, no blow.
Bypassed tool at 20 mins, few bubbles.
Rec. 8' mud. ICIP 15#/30 min., IFP 0#,
FFP 15#, FCIP 15#/30 min.

TOPS:

Stone Corral-Electric Log	717
Topeka	2607
Heebner	2928
Leavenworth	2932
Snyderville	2935
Toronto	2946
Douglas	2957
Brown Lime	3027
Lansing	3044
Base Kansas City	3290
Marmaton	3290
Conglomerate	3300
Arbuckle	3303

DST #1 3047-55, op 1½ hrs, small blow which
died in 45 min, flushed tool at 60 mins
very weak blow for 14 mins. rec. 20'
very slightly oil cut mud. ICIP 90#/30 min.
IFP 0#, FFP 20#, FCIP 40#/30 mins.

DST #2 3111-25, op 1½ hrs, fair blow thruout
test. Rec. 410' salt water - no oil or gas.
ICIP 1065#/30 min. IFP 0#, FFP 150#,
FCIP 1015#/30 mins.