

*Plotted*  
*36-17-11W*

THE TEXAS COMPANY.  
 F. Bloomer No. 6.

SEC. 36 T. 17 R. 11W  
 SE NE NE  
 Approx 330 fr S & EL in N $\frac{1}{2}$   
 NE $\frac{1}{4}$

County. Barton

Total Depth. 3286'  
 Comm. 2-19-37 Comp. 3-27-37  
 Shot or Treated.  
 Contractor. Helmerick & Payne, Inc.  
 Issued. 5-15-37 Rotary O-3274  
 Cable 3274-3286

CAS ING:  
 10" 179'  
 7" 3272'



Elevation.

Production. Pot. 1513 B.  
 after acid.

Figures Indicate Bottom of Formations.

surface clay	70
shale & clay	179
shale & shells	360
red rock, shale	610
red rock, shells	840
shale	965
shale & shells	1095
salt	1255
salt & shale	1330
shale & shells	1395
lime	1440
lime & shale	1605
lime	1830
lime hrd	1848
lime & shale	2046
shale	2090
lime & shale	2184
shale	2230
lime & shale	2547
lime	2587
lime & shale	2667
lime	2699
lime & shale	2728
lime	2754
lime & shale	2834
lime	2882
lime & shale	2932
shale	2990
lime & shale	3070
lime hrd	3097
lime & shale	3247
lime	3274
Siliceous lime	3286
Total Depth.	

Production: Pump Pot. 1513 B.  
 after acidizing.