

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


SKELLY OIL CO.
J.B.Bloomer No. 1.

SEC. 36 T. 17 R. 11W
NW SW NE
330' fr NL 330' fr WL

Total Depth. 3270'
Comm. 8-3-36 Comp. 8-23-36
Shot or Treated.
Contractor. Triangle Drlg. Co.
Issued. 10-17-36 Rotary O-3270
CASING:

County. Barton

OCT 17 1936



12 1/2" 3265'
7 " 3265'

Elevation.

Figures Indicate Bottom of Formations. 24 hrs; Est. 10,000 Gas.

Production. Pump 2297 B

surface sand & clay	30
shale & shells	200
shale & shells	240
sand	250
shale blue	345
red beds and shells	545
red beds & shale blue	595
anhydrite	620
shale, red beds & shells	870
shale blue & shells	1020
shale & shells	1090
salt & shells	1360
lime & shale	1590
sand, shale & lime	1615
shale & lime shells	1660
lime & shale	1720
lime, shale & sand	1785
lime & shale	1930
shale & lime shells	2050
lime & shale	2240
shale, lime & sand	2247
Steel line correction 2247-2248 1/2'	
shale, lime & sand	2305
sand, shale & lime shells	2430
shale & lime	2590
lime	2711
Steel line correction 2711-2713	
lime	2713-2917
Steel line correction 2917-2920	
lime	3266

Lansing Limestone Top 2985'

Siliceous Limestone Top 3265-3270'

Oil from 3265-3270

Main body pay formation.

Top Lansing lime 2985
Steel lined hole at 3152'
cored 3266-3272 - Recovered 5'
4" shale grey
20" dense grey dolomite - Saturated

24" dense grey dolomite
Slight saturation & porosity
12" brown porous dolomite. Saturated.
Steel line Correction 3272-3270
Top Siliceous lime 3265

Total Depth 3270'