

*Plotted gas*  
**36-17-11W**


SKELLY OIL CO.  
 J.B. Bloomer No. 2.

SEC. 36 T. 17 R. 11W.  
 NE SW NE  
 990' fr WL

Total Depth. 3264 SLM  
 Comm. 9-17-36 Comp. 10-11-36  
 Shot or Treated.  
 Contractor. Olson Drlg. Co.  
 Issued. 11-21-36 Rotary 3264 SLM

County. Barton

NOV 21 1936



CASING:

12 1/2" 186'  
 7" 3259 1/2'

Elevation.

Pot. 2750 B. Pump  
 Production. 2750 B. Pump

Figures Indicate Bottom of Formations. 24 hr., Est. 10,000 Gas.

surface soil	25
clay, shale & shells	193
shale	330
red bed	408
shale	1061
shale & shells	1348
Trace of salt at 1126'	
lime	1379
brkn lime	1480
brkn lime & shale	1574
brkn lime	1592
lime	1663
brkn lime	1698
lime	1701
lime & shale	1771
lime	1930
brkn lime	1945
lime	2004
brkn lime	2086
brkn lime & shale	2196
brkn lime	2247
shale	2267
lime	2490
brkn lime	2549
lime	2958
brkn lime & shale	2989
shale	3002
lime	3035
brkn lime	3075
shale	3103
lime	3134
shale	3137
lime	3167
shale	3174
lime	3262
Top Siliceous lime	3259 1/2 SLM
Cored	3262-65
Rec. 3' All brown porous saturated dolomite	
SLM Correction	3265-64
Total Depth.	3264

Siliceous Lime Top 3259 1/2-64

~~Oil from 3202-64~~