

Plot 11/13/37

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

36-17-11W


SKELLY OIL COMPANY.
J. B. Bloomer No. 5

SEC. 36 T. 17 R. 11 W.
NW SE NE

Total Depth. 3275
Comm. 11-25-36 Comp. 12-15-36
Shot or Treated 1000 gal acid.
Contractor Olson Drlg Co.
Issued 1-23-37

County . Barton.

JAN 23 1937



Rotary 0 to 3273
Cable 3273-3275
CASING.

12 1/2" 205'
7" 3269'

Elevation.

Production. Pot. 2750 B.
Est 10,000 G.

Figures Indicate Bottom of Formations.

surface soil and clay	90
shale and lime shells	208
shale and shells	562
shale	570
shale and lime shells	944
shale and shells	1154
shale	1290
lime	1342
broken lime	1460
lime	1504
broken lime	1699
lime	2280
shale and lime shells	2334
shale	2375
broken lime	2505
lime	2532
lime hard	2562
shale	2567
shale and shells	2592
lime	2912
lime and shale	2978
lime	3049
shale and shells	3068
lime	3074
lime	3088
slight show gas and oil	3074-3088
broken lime and shale	3102
lime	3158
broken lime	3169
lime hard	3227
lime	3245
lime hard	3263

cored 3263-73 Rec 10'

3263-69 shale.

3269-73 c. xln. dolo.

Top Siliceous lime 3269 SLM Filled up 1800' 3 hrs.

lime 3275

Total Depth.

Filled up 3100'

Potential 2750 bbls oil and no wtr 24 hrs -