

26-17-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MORRIS SITRIN ETAL
Farm- Staatz No. 3

SEC. 26 T. 17 R. 11W
SE NW NW

Total Depth. 3327'
Comm. 10-27-52 Comp. 11-5-52
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 2-20-54

County Barton
KANSAS



CASING:

8 5/8" 215' com w/125 sx
5 1/2" 3317' com w/125 sx

Elevation. 1856

Production. Dry

Figures indicate Bottom of Formations.

sand rock	40
shale	154
green shale	160
red bed	215
shale & shells	270
sand	290
red bed & shale	515
sand & shells	675
anhydrite	697
shale & shells	1435
lime	1940
lime & shale	2150
shale	2385
lime & shale	2766
lime	3327 R.T.D.
Total Depth.	

Tops:

Lensing	3029
Conglomerate	3304
Arbuckle	3315

Drill Stem Tests:

#1 3099-3110, open 30 mins., rec. 720'
salt water, 330' gas cut mud, BHP 1000#.

#2 3317-3327, open 2 hours, rec. 35' oil,
135' oil cut mud, BHP 875#.