

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 412 Union National Bldg., Wichita, Kansas


8-17-11W

REPUBLIC NATURAL GAS CO.
 Radenberg No. 2.

SEC. 8 T. 17 R. 11 W
 CSE SE

Total Depth. 3308'
 Com. 3-5-43 Comp. 3-30-43
 Shot or Treated. 3-29-43 500 Gals.
 Contractor. E.K. Carey
 Issued. 5-15-43

County. Barton



CASING:
 10 3/4" 238' Cem.
 7" 3302' Cem.

Elevation.

Production. Pot. 73 B.
 No wtr

Figures Indicate Bottom of Formations.

soil & clay	0-20
gravel	35
shale	165
sand	180
shale & shells	506
red rock & shale	694
anhydrite	720
shale & shells	951
shale & lime	1116
shale & shells	1210
salt & shale	1270
shale & shells	1360
lime	1532
lime & shale	1603
lime	1670
lime & sdy lime	1802
lime	1866
lime & shale	2145
lime & shale	2380
shale	2470
shale & lime	2515
lime	2602
lime & shale	2627
lime	2631
shale	2660
shale & lime	2855
shale	2875
lime	2899
lime hd	2914
lime	2949
lime & shale	3019
lime	3122
lime sft	3153
lime hd	3165
lime & shale	3194
shale strks & lime	3226
lime	3300
Arbuckle	3308
Total Depth.	

5 BOPH. Bailed well for 10 hrs, & after letting well set for 10 hrs had a 1600' fillup of oil in the csg. Sampled btm of hole & no wtr show. Ran tbg & acidized well w/ 500 Gals. Acid, & well swbd 15 BPH on a 10-hr swb test after cleaning out the acid wtr.

Tops: Lansing K.C. 3019
 Arbuckle 3302 DF
 Penetration 6'

Drld in w/cable tools from 3302-06 & had a fillup of