


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

THE TEXAS CO.
F.F. Burmeister "A" No. 3

SEC. 2 T. 17 R. 11W
CEL NE SW
660'fNL 330'fEL SW $\frac{1}{4}$

Total Depth. 3396
Comm. 12-8-40 Comp. 12-22-40
Shot or Treated.
Contractor. Helmerich and Payne, Inc.
Issued. 2-1-41

County Barton.



CASING. Rotary.

103/4" 315' cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

sand and gravel	45
shale and sholls	200
sand	230
lime	325
shale shells & sand	525
red bed and shale	630
red bed	710
anhydrite	740
shale and shells	903
shale	965
broken lime	995
shale	1040
sand	1070
shale and shells	1190
salt and shale	1240
shale and lime	1390
shale and shells	1420
broken lime	1460
lime	1550
shale and shells	1725
lime	1740
shale	1750
broken lime	1785
lime	1955
shale	2005
lime	2040
sdv lime & shale	2125
shale	2215
shale and lime	2390
lime	2495
lime broken	2565
shale	2610
lime and chert	2670
lime	2972
lime and shale	3095
lime	3326
lime and conglomerate	3355
conglomerate	3396
Total Depth.	

Top Lansing 3055
Conglomerate 3325
Arbuckle 3390
No shows of oil

Well temporary abandoned, later to be used for salt water disposal well if needed. Hole plugged with heavy mud, out off 103/4" surface pipe and welded plate over same. All of surface pipe left in hole 315'