

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas


Company - TEXAS COMPANY
 Farm - F. Burmeister "B" No. 5

SEC. 2 T. 17 R. 11W
 SE NW SE

Total Depth. 3384
 Comm. 12-31-49 Comp. 1-16-50
 Shot or Treated.
 Contractor. Stickle Drlg. Co.
 Issued. 2 - 11 - 50

County. Barton

KANSAS



Elevation. _____

Production. 180.90 bbls oil
 no wtr.

CASING:

8 5/8" 734' cem. w/300 sx.
 5 1/2" 3375' cem. w/100 sx.

Figures indicate Bottom of Formations.

clay & sand	120
shale & shells	255
sand & shale	307
lime, shells & shale	490
shale & shells	560
red bed & shells	725
anhyd.	765
shale & lime shells	1275
salt & shells	1470
lime & shale	1580
lime, sand & shale	1685
shale & lime	2760
lime	2981
lime & shale	3085
lime	3369
lime & congl.	3374
lime	3384
Total Depth	

Tops:

Heebner	2962
Brown Lansing	3062
White Lansing	3075
Congl	3357
Arbuckle	3373

1-10-50 Ran D.S.T. # 1, packer at 3261',
 10' of anchor. Open 33 mins., rec. 30' of
 drilling mud and well blown for 22 mins.
 BHP 65# PSI in 10 mins.

1-16-50 Drilled cem plug & cleaned out to
 3379'. No show of oil. Drilled deeper 3384'
 & tested 1/2 bbl. oil, no wtr. per hr. Acidized
 w/500 gals acid, max. press. 1000# PSI.
 Dropped 350# PSI in 5 mins, to vacuum in
 20 mins.

1-17-50 Swabbed well down & tested 156.60
 bbls. oil, no wtr. in 18 hrs.

1-19-50 Pmpd. 5 1/2 bbls oil, no wtr. per hr.

Rotary Total Depth-- 3379'