

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

THE TEXAS COMPANY.  
H. Disque No. 7.

SEC. 3 T. 17 R. 11W.  
NW NE SW  
330' f NL 990' f EL SW $\frac{1}{4}$

Total Depth. 3306.  
Comm. 12-9-40 Comp. 12-23-40  
Shot or Treated. No acid.  
Contractor. Helmerich and Payne, Inc.  
Issued. 2-22-41

County Barton.

Rotary 3296  
Cable 3306  
10" CASING. 283' Cemented.  
7" 3296' Cemented.



Elevation.

Production Pot. 5028 B.  
no wtr. Depthograph.

Figures Indicate Bottom of Formations.

|                        |      |
|------------------------|------|
| surface loam and shell | 120  |
| shells sand and shale  | 210  |
| shale and shells       | 283  |
| shale shell & red bed  | 690  |
| anhydrite              | 729  |
| red bed and anhydrite  | 799  |
| red bed shale & anhyd. | 825  |
| shale and shells       | 1147 |
| salt and shale         | 1390 |
| anhydrite and shale    | 1505 |
| shale and lime         | 1705 |
| shale lime and sand    | 1865 |
| lime & shale           | 2405 |
| broken lime            | 2545 |
| lime and shale         | 2666 |
| broken lime            | 2736 |
| lime                   | 2932 |
| shale and lime         | 3044 |
| lime                   | 3252 |
| lime and shale         | 3295 |
| lime Arbuckle          | 3306 |
| Total Depth.           |      |

Top Arbuckle 3296