


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

THE TEXAS COMPANY.
H. Disque No. 8

SEC. 3 T. 17 R. 11W.
SE NW SW
990' f NL 990' f WL SW $\frac{1}{4}$

County Barton.

Total Depth. 3307
Comm. 1-5-41 Comp. 2-1-41
Shot or Treated. 1000 gal acid.
Contractor. Helmerich & Payne, Inc.
Issued. 3-8-41.



CASING. Rotary 3289
Cable 3307

103/4" 235' 7" 3289' cemented.

Elevation.

Production. Pot. 2046 B.
No wtr.

Figures Indicate Bottom of Formations.

clay yellow	15
shale blue	82
shale grey	180
water sand	185
yellow shale & clay	227
red rock	235
shale and shells	460
shale red	510
red bed and shells	685
lime	712
shale and shells	1000
lime hard	1006
lime and shells	1020
shale	1100
salt	1280
shale and shells	1370
shale	1390
lime	1450
lime shale broken	1650
lime	1655
shale and shells	1710
lime	1730
shale	1755
lime broken	1813
lime	1855
shale and lime	2043
lime and shale broken	2146
lime and shale	2280
shale	2360
lime	2430
lime and shale	2825
lime	2910
shale	2925
shale and Br. lime	3008
shale	3015
lime	3055
lime & shale breaks	3083
lime	3295
Arbuckle lime	3300
lime	3307
Total Depth.	

Top Arbuckle 3289

First test 1715 bbls oil 1-28-41. Took retest 1-31-41 after acidizing with 1000 gal of acid. retest 2046 bbls oil and no wtr.