


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

OHIO OIL CO.
Cynthia Riemann No. 1.

SEC.4 T.17 R.11W
CSL SW SW

Total Depth. 3339' PB 3327'
Comm. 3-26-41 Comp. 4-25-41
Shot or Treated. 500 Gals. Acid
Contractor. Triangle Drlg. Co.
Issued. 7-26-41

County. Barton



CASING:
8 5/8" 291' Com.
4 1/2" 3307'

Elevation.

Production. Pot. 360 B.

Figures Indicate Bottom of Formations.

shale sdy	80	Completed thru perforations
shale & shells	175	at 3320-23 $\frac{1}{2}$
sand	250	225' oil 3 minutes
shale & shells	530	1000' oil 30 minutes
red bed	610	1400' oil 3 hrs
shale & shells	700	1950' oil 6 hrs
anhydrite	730	
shale & shells	845	
shale & red bed	875	
shale & shells	980	
shale	1060	
shale & shells	1200	
salt	1353	
salt & shells	1385	
anhydrite	1465	
anhydrite & shale	1535	
shale-lime brkn	1575	
lime	1610	
lime & shale	1675	
lime & pyrite of iron	1685	
lime & shale	1750	
lime	1825	
lime brkn	1865	
lime & shale	2010	
lime	2055	
lime & shale	2400	
shale & shells	2470	
lime	2490	
shale & lime	2675	
lime	2942	
shale & shells	2980	
shale	3010	
lime KC	3256	
shale & brkn lime	3269	
lime	3294	
conglomerate	3300	
Simpson sdy shale	3309	
cored lime	3339	
Total Depth.		

Plugged back to 3327

Tops: Kansas City 3011
Conglomerate 3291
Re-Work. Simpson 3301
Arbuckle 3306