

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company CITIES SERVICE OIL COMPANY
Farm Kirmer No. 1

SEG. 8 T. 17 R11W
CE $\frac{1}{2}$ NE SW
660' S & 330' W of center

County. Barton
KANSAS



Total Depth. 3389'
Comm. 2-5-48 Comp. 3-28-48
Shor or Trated. See Below
Contractor Corbett-Barbour Drlg. Co.
5-8-48

CASING:

8-5/8" 314' Cem. W/175 Sx.
4-1/2" 3352' Cem. W/ 75 Sx.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

clay & shale	70
shale & shells	273
shale, shells & sand	316
pyrite & sand	340
shale	470
shale & shells	750
anhydrite	780
shale, shells & redbed	990
shale & shells	1140
shale & lime	1385
salt	1420
shale & lime	1470
lime	1600
lime & shale	1716
shale & lime	1800
lime	1835
lime & shale	2285
shale & lime	2430
shale	2475
lime & shale	2762
lime	2990
lime & shale	3045
lime	3147
lime & shale	3240
lime	3293
lime & shale	3352
lime	3356
3356 RTD = 3360 SLM	
lime	3389
Total Depth	

Tops:
Corr. Lansing 3090
Corr. Arbuckle 3349
Penetration 40

Rainbow show oil & 1 $\frac{1}{2}$ gals. wtr
each 2 hrs. for 10 hrs. at 3360.

Perf. 60 shots 3352-59 to remove
cement from sides of hole.

Jetted hole W/500 gals. acid.
3-21-48 - Az. W/500 gals.

Deepened 3360-73: $\frac{1}{2}$ BOFH for
8 hrs. at 3370-3373.

3-26-48 Ax. 500 gals., no increase

Deepened 3373-89; show wtr 3383-86.

600' wtr in 1 hr at 3386-3389
1000' wtr in 5 hrs. at 3386-3389