


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- Birmingham-Bartlett Drlg.,
Farm- Kroutwurst No. 3

SEC. ⁶ T. 17 R11W
W/2 SE SE

Total Depth. 3277'
Comm. 9-21-57 Comp. 9-29-57
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg.,
Issued. 11-9-57

County Barton
KANSAS



Elevation. 1840 R. B.

Production. 150 BOPD

CASING:

8 5/8" @ 261' W/185 sks. cem.
5 1/2" @ 3271' W/75 sks. cem.

Figures Indicate Bottom of Formations.

surface clay & shale	130
shale	258
shale streaks of sand	310
shale & shells	420
red bed & shells	650
red bed	685
Anhydrite	696
shale & shells	1365
lime & shale	3130
lime	3277
Total Depth	

Scout Tops:

Anhydrite	685
Heebner	2881
Br. Lime	2981
Lansing	2997
Base Kansas City	3259
Arbuckle	3268
Rotary T.D.	3277
C.T. T.D.	3277

DST: #1: 3268-77. Open 1 hr. Rec.
460' oil, 215' gas. BHP 1000#

Drilling-In Info:

Drilled plug & cleaned out to 3277'.
Filled up 300' oil 1st hr., 450' 2nd
hr. while bailing. Tested 8 BOPH
natural, no water. Put well on pump.