


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CARTER OIL CO.-PHILLIPS PETRO.CO.  
Kraft No. 7

SEC. 10 T. 17 R. 11W.  
CW $\frac{1}{2}$  NE NE

Total Depth. 3276  
Comm. 3-2-41 Comp. 4-1-41.  
Shot or Treated.  
Contractor. Iron Drilling Co.  
Issued. 4-19-41

County Barton.



Rotary.

CASING.

85/8" 234' 5 $\frac{1}{2}$ " 3273 $\frac{1}{2}$

Elevation.

Production. Pot. 5227 B.

Figures Indicate Bottom of Formations.

shale and shells	242
shale	670
anhydrite	675
broken limestone and shale	835
limestone	875
shale and shells	1110
salt	1345
limestone	1385
shale and limestone	1587
limestone hard	1620
shale and shells	1670
sand	1690
shale and shells	1720
sand	1735
sticky shale	1811
limostone	1844
shale and shells	1980
shale	1993
shale and shells	2065
shale	2140
limestone and shale	2438
limestone	2463
limestone and shale	2525
shale and shells	2579
limestone and shale	2670
limestone	2816
limestone and shale	2840
limestone	2878
shale and limestone	2915
shale and shells	2945
limestone	2957
limestone and shale	2986
shalo	2995
limestone	3028
shale and limestone	3062
limestone	3123
limestone and shalo	3165
limestone	3250
limestone and shale	3273
limestone	3276

Total Depth.