

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CARTER OIL CO.  
J. Stueder No. 1.


SEC. 10 T. 17 R. 11W.  
SEc SE  
330 fr S & E. lines.

Total Depth. 3335  
Comm. 12-23-37 Comp. 1-14-38  
Shot or Treated.  
Contractor.  
Issued. 2-12-38

County Barton.

CASING.

103/4" 232'  
6" 3325'



Elevation.

Production. Pot. 1607 B.

Figures Indicate Bottom of Formations.

shale and shells	550
shale and lime	640
shale and shells	750
broken lime shale	1006
shale and shells	1133
shale shells salt	1329
salt shale	1467
shale and shells	1630
lime	1691
shale and shells	1792
shale	1824
lime	1950
shale and shells	1976
lime	1991
shale	2009
lime	2070
shale and shells	2093
shale	2165
shy shale	2245
lime and shale	2262
shale and shells	2393
shale and lime shells	2468
shale and shells	2630
lime	2670
shale	2680
shale and shells	2710
lime	2853
broken lime	2867
lime	2956
shale and shells	2976
broken lime shale	3016
shale and shells	3022
lime	3137
cored lime	3147
lime	3250
cored lime	3258
lime	3290
cored lime	3303
cored lime	3306
lime	3307
cored lime	3313
lime	3314
cored lime shale	3323
shale	3325
cored lime	3335

Total Depth.

Arbuckle 3325-3335

Slight show oil in Kansas City Lime