


CARTER OIL CO.  
 C. Kroutwurst No. 3.

SEC. 10 T. 17 R. 11W  
 NE SW NW

Total Depth. 3372' PB 3346'  
 Comm. 6-4-41 Comp. 7-30-41  
 Shot or Treated. 2000 Gals. Acid  
 Contractor. Iron Drlg. Co.  
 Issued. 8-23-41

County. Barton



CASING:  
 8 5/8" 225'  
 5 1/2" 3306'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay & post rock	90	1st acid 500 gals.
clay & gumbo	125	2nd acid 1500 gals.
shale	169	
sand, lime, shale	227	Tops: Topeka 2680
shale, shells, red rock	543	Kansas City 3023
redrock & shale	675	Arbuckle 3308
anhydrite	705	
sand, shale, red beds	845	slight sh oil 2950-55
redbeds, shale, shells	1148	slight sh oil 3041-45
salt & shell	1374	slight sh oil 3072-74
shale	1384	sh oil 3115-18
lime	1409	slight sh oil 3210-26
lime & shale	1487	sh oil 3308-11
shale	1548	
shale sdy	1600	
lime	1635	
lime & shale	1830	
shale gy sft	1890	
shale sticky & shell	1902	
lime & shale brks	1930	
shale	1951	
shale sticky	1952	
lime brkn	2047	
shale & lime	2305	
shale	2378	
shale & sdy lime str.	2464	
lime & shale	2545	
lime brkn	2575	
shale & lime	2642	
shale dk gy	2657	
lime & shale	2705	
shale & shell	2718	
lime & shale	2740	
lime brkn	2807	
lime	2838	
lime & shale brks	2890	
shale & shell	2903	
lime brkn	2944	
lime	2978	
shale	3025	
shale, red bed, shell	3044	
lime, shale brks	3090	
shale	3116	
lime	3119	
shale	3122	
lime	3138	
lime sft & blk & gr.		
shale	3154	
lime	3162	
lime & shale	3191	
lime	3303	
lime & shale	3308	
lime Arbuckle	3311	
lime	3367	
shale	3369	
lime	3372	
Total Depth.		

Plugged back to 3346