


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. CITIES SERVICE OIL CO.
Farm. Hogan "A" No. 13

SEC. 11 T. 17 R. 11W
C N $\frac{1}{2}$ S $\frac{1}{2}$ N $\frac{1}{2}$
990' N of center

Total Depth. 3351 SLM
Comm. 8-15-53 Comp. 8-26-53
Shot or Treated.
Contractor. Holm Drilling Co.
Issued. 11-7-53

County Barton
KANSAS



Elevation. 1923 GL

CASING:
8 5/8" 453' cem. w/250 sx
5 1/2" 3350' cem. w/150 sx

Production. Phy. Pot. 44 Oil,
44 wtr, 24 hrs.

Figures indicate Bottom of Formations.

lime	50
shale & sandy shale	300
shale & sand	400
sand	415
shale	470
red bed	630
red bed & shale	700
anhydrite	750
shale & shells	1270
shale & lime	1605
lime, shale & shells	1850
shale	2045
lime & shale	2520
shale & shells	2740
lime & shale	2910
lime	2967
lime & shalo	3116
lime 3355 RTD=3350 SLM 3355	
lime	3351 SLM
Total Depth	

TOPS (CORR.):
Lansing 3074
Conglomerate 3341
Arbuckle 3349

Penetration 2'

Fillup:
195' oil in 35 mins.
700' oil in 50 mins.
1180' oil in 1 hr. 35 min.
1345' oil in 1 hr. 50 min.