

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL COMPANY

SEC. 12 T. 17 R. 11W

FARM Hogan "A" NO. 11

LOC. NW NE NW
330' S & 990' W of N/4 Cor.

TOTAL DEPTH 3422

COMM. 8-21-50

COMP. 9-10-50


SHOT OR TREATED 2500 gals. acid

CONTRACTOR Lohmann-Johnson Drlg. Co., Inc.

ISSUED 12-16-50

COUNTY Barton

KANSAS



CASING

8 5/8" 360' cem. w/200 sx

5 1/2" 3410' cem. w/125 sx

ELEVATION 1965

PRODUCTION 96 oil & NW/24 hrs
(Phy. Pot.)

FIGURES INDICATE BOTTOM OF FORMATIONS

shale	190
sand	345
shale & shells	362
shale & redbed	650
shale & shells	1400
broken lime	1825
lime	1900
broken lime	2335
lime & shale	2840
lime	3043
lime & shale	3139
lime	3415
3415 RTD = 3411 SLM	
lime	3422
Total depth	

Tops: (Corrected)

Topeka	2759
Lansing	3111
Eros. Arbuckle	3405
Arbuckle	3409
Penetration	13'

Remarks:

Fillup: 195' oil in 4 hrs. at 3419
9-7-50 Acidized 1000 gals. at TD 3419
9-9-50 Pump. 76 oil, no wtr. 20 hrs.
9-10-50 Deepened 3419-22
9-11-50 Acidized 1500 gals.