

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - SUNRAY OIL CORP.
Farm - Lewis Andrea No. 5

SEC. 12 T. 17 R. 11W
NW NE NE

Total Depth. 3404
Comm. 5-8-50 Comp. 5-22-50
Shot or Treated.
Contractor. Mouser Dr'lg. Co.
Issued. 9-8-51

County. Barton
KANSAS



CASING:
8 5/8" 269'
5 1/2" 3403'

Elevation. _____

Production. Phy. Pot. 425 BOPD
35% wtr

Figures Indicate Bottom of Formations.

surface	222
sand & shale	235
sand	252
shale & shells	380
sand	410
shale	515
shale red	715
anhydrite	740
shale	925
shale & shells	1125
salt	1275
shale & shells	1420
lime & shale	1482
shale & lime	1615
lime & shale	1760
lime	1860
lime & shale	2075
shale & shells	2085
lime & shale	2430
shale & shells	2630
lime & shale	2768
lime	2946
lime & shale	3060
lime	3172
lime porous	3200
lime	3370
conglomerate	3404 RTD
Total Depth	

Tops:
Heebner Shale 2960
Iatan 3061
Lansing 3080
Conglomerate 3370
Arbuckle 3402

DST: 3160-72 open 1/2 hr.
gas in 12 min., rec. 70' oil
& gas cut mud and 480' gassy
oil and 540' slt. wtr. 595#;
DST 3225-411' open 45 min.
gas in 40 min., rec. 85' oil,
140' oil and gas cut mud, 610#;
DST: 3265-76' open 45 min. rec.
65' heavy oil and gas cut mud.
485#;