

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SUNRAY OIL CORP.

SEC. 12 T. 17 R. 11W
LOC. SE NE NE

FARM Andrea

NO. 7

TOTAL DEPTH 3411

COMM. 1-27-51

COMP. 2-13-51

SHOT OR TREATED

CONTRACTOR Mouser Drlg Co.

ISSUED 4-7-51

COUNTY Barton



CASING

10-3/4" 371'

5-1/2" 3409'

ELEVATION 1943 RB

PRODUCTION Phy. Pot. 318 BO
& 15% wtr

FIGURES INDICATE BOTTOM OF FORMATIONS

surface rock	50
shale & shells	320
sand	335
red bed & shells	371
red bed	705
anhydrite	735
shale & shells	1040
salt	1270
shale & shells	1450
shale & lime	1525
lime & shale	1675
shale & lime	1720
sandy lime	1750
lime	1900
lime & shale	2000
shale & shells	2375
lime & shale	2430
shale & lime	2565
lime & shale	2630
lime	2985
shale	3054
lime	3366
conglomerate	3407
arbuckle	3411
Total Depth	

Tops:

Heebner	2953
Iatan	3054
Lansing	3071
Conglomerate	3366
Arbuckle	3407

DST: 3157-65, open 1 hr. rec.
gas 34 min. 180' free oil, 45'
heavy O & GCM; BHP #380;
CO 3373, perf. 21-263-69; 1000
A; Test 15 GWPB; PB 3236 16/3159-
63; Test 1 GOPH; 3000 A; Phy. Pot.
318 BOPD plus 15% wtr.