

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


THE TEXAS COMPANY.
M. Peterman No. 1.

SEC. 13 T. 17 R. 11W,
NEc SE
Approx. 330' fr N & E.L.

Total Depth. 3325
Comm. 9-7-36 Comp. 1-20-37
Shot or Treated. 1000 gal.
Contractor. Parker Drlg Co.
Issued. 2-27-37

Rotary 3288
Cable 3325

County. Barton.



CASING.

10" 198' 7" 3288'

Elevation.

Production. Pumping 261 B.O.
13½ B.W.

Figures Indicate Bottom of Formations.

surface clay and shells	205	lime	2638
red bed	260	shale and lime shells	2689
shale and shells	290	lime and shale	2744
shale grey	415	lime	2792
red bed	615	broken lime	2828
lime hard	635	lime	2875
shale	845	broken lime	2955
shale and shells	1065	shale	2980
salt	1115	broken lime	3010
shale and salt	1210	lime	3090
shale and shells	1330	broken lime	3103
lime broken	1370	lime	3115
shale	1394	lime and shale	3157
lime	1407	lime	3237
shale and shells	1590	lime and shale	3282
lime and shale	1644	chat	3289
sand	1654	lime	3300
lime	1680	lime and sand	3312
sand hard	1690	lime	3325
sand	1708	Total Depth.	
broken lime	1723		
shale and shells	1760		
shale	1770		
lime	1898		
shale	1912		
broken lime	1935		
lime	1950		
red bed	1960		
shale	2020		
lime and shale	2110		
shale and shells	2210		
shale	2230		
lime	2245		
shale and lime	2340		
Porous lime	2355		
shale	2385		
lime	2408		
lime broken	2480		
shale and lime	2540		
lime	2545		
shale	2570		
lime	2590		
shale and shells	2625		