


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - TEXAS CO.  
Farm - M. Peterman No. 3.

SEC. 13 T. 17 R. 11 W  
CN $\frac{1}{2}$  SW SE  
999'f SL 660'f WL SE $\frac{1}{4}$

Total Depth. 3329'  
Comm. 11-19-43 Comp. 12-8-43  
Shot or Treated.  
Contractor. Kiowa Drlg. Co.  
Issued. 1-8-44 Rotary O-3329

County. Barton  
KANSAS



CASING:  
8 5/8" 259' Cem.  
5 1/2" 3322' Cem.

Elevation. \_\_\_\_\_

Production. Pmp Pot. 238 BO  
No wtr

Figures Indicate Bottom of Formations.

clay & sand	60
red rock & sand	190
shale & shells	259
shale	330
shale & red bed	635
anhydrite	660
shale & red bed	740
shale & shells	1100
salt	1200
shale & shells	1350
lime & shale	1425
shale & shells	1740
lime & shale	1784
lime	1925
lime & shale	2346
shale	2374
shale & lime	2410
shale & shells	2510
shale & lime	2648
lime	2700
lime brkn	2730
lime	2990
lime & shale	3045
lime	3145
lime brkn	3225
lime	3300
conglomerate	3320
lime Arbuckle	3329
Total Depth.	

Tops: Lansing	3018
Conglomerate	3292
Arbuckle	3320