

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - TEXAS CO.
Farm - M. Peterman No. 4.

SEC. 13 T. 17 R. 11 W
C N $\frac{1}{2}$ SE SE

Total Depth. 3385'
Comm. 1-18-44 Comp. 2-22-44
Shot or Treated.
Contractor. Kiowa Drig. Co.
Issued 3-25-44

County. Barton
KANSAS



CASING:
8 5/8" 268' Cem.
5 1/2" 3384' Cem.

Elevation. _____

Production. Dry-Temp. Abnd.

Figures Indicate Bottom of Formations.

surface & shale	120	Tops:
shale & sand	268	Lansing 3010
shale	590	Congl. 3296
shale & shells	1190	Arbuckle 3329
salt	1305	
shale & lime	1610	
sdv lime	1660	
lime	1710	
shale & lime	2380	
sdv shale & shells	2460	
shale & shells	2535	
lime & shale	2580	
lime	3006	
shale & lime	3067	
lime	3385	
Total Depth.		

Cored 3332-39 some porosity
spotted w/oil

Perforations:

3330-37 w/12 shots - filled
up 1200' wtr in one hr
3260-69 w/10 shots
3230-38 w/9 shots
3239-45 w/6 shots
3225-29 w/4 shots
3105-14 w/9 shots
3187-3202 w/12 shots
no sh oil or wtr

Acidized w/1000 Gals. 15%
acid, swbd & bailed approx.
4 gals. wtr per hr

Acidized w/3000 Gals. 15%
acid, swbd hole dry in 2
hrs., 6 BW & 1 BO in 3
hrs

Well temporarily abnd