

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company THE TEXAS COMPANY
Farm M. Peterman No. 5

SEC. 13 T. 17 R. 11W
CS₂ SW SE

Total Depth. 3318'
Comm 1-30-48 Comp. 2-18-48
Shot or Treated.
Contractor. Stickle Drilling Company
Issued 3-27-48

County. Barton
KANSAS



CASING:
8-5/8" 634' Cem. w/325 sx
5-1/2" 3316' Cem. w/150 sx

Elevation. _____

Production. D.D. Pot. 1745 BO
and no water

Figures Indicate Bottom of Formations.

shale & shells	265
sand, shale & shells	420
shale & shells	628
anhydrite	660
shale & shells	1080
salt, shale & shells	1260
shale & shells	1340
shale, lime & shells	1370
shale & shells	1410
lime & shale	1720
lime brkn	1770
lime & shale	1845
shale & lime	2130
shale & shells	2240
shale & lime	2500
shale	2545
lime & shale	2735
lime	2910
shale & lime	3005
lime	3275
conglomerate	3313
lime	3318
Total Depth	

Tops:
Topeka 2628
Lansing 3006
Arbuckle 3313

Remarks:
2-16-48 Swabbed 5 BOPH-natural.
acid. w/500 gal. Maximum pressure
275#, dropped to 225# during job,
zero in 5 minutes after job. (Used
88 BO load) swabbed 230 BO in 3 hrs.
4.2 Bbls new oil.

Draw Down Production first 24 hours:
1745 BO, no water.