


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

TRANSWESTERN OIL CO.
J.R. Myers No. 2

SEC. 13 T. 17 R. 11W.
CWL NW NE

Total Depth. 3323
Comm. 5-4-41 Comp. 5-22-41
Shot or Treated.
Contractor.
Issued. 6-28-41

County Barton.



CASING.

85/8" 249' cemented.
5 1/2" 3318' cemented.

Elevation.

Production. Pot. 2951 B.

Figures Indicate Bottom of Formations. No water, Echometer.

surface	40
sand and shale	210
shale and shells	409
shale sand and red bed	638
red bed	780
shale and shells	1095
shale and salt	1300
shale and limo	1440
broken lime	1581
shale and red bed	1598
limo and shale	1726
sdv limo	1780
lime and shale	2150
shale and shells	2222
shale and lime	2364
sticky shale	2420
lime and shale	2431
lime	2469
lime and shale	2680
lime (Topeka)	2806
lime and chert	2863
lime hard	2887
lime and shale	3023
lime K.C.	3103
lime hard	3107
lime soft	3132
lime and shale	3165
lime	3255
lime and chert	3318 T.R.D.
STD tools	3322
hard dolomite	3323
Total Depth.	

Top of Arbuckle lime 3315' T.D. 3318, All Measurements
Rotary 3316-3318 Dol. hard, very hard. 3318-3321 softer
some nice brown chunks. Hole filled up 1200' in 1 hr.
1500' in 1 1/2 hours, 2000' in 2 1/2 hours. 2500' 3 1/2 hours, 3321-3323
hard dolomite, no porosity, 3323 T.D. after drilling completed
and hole cleaned. Dumped 35 gal 30% acid on bottom of dump
bailer. Let stand 3 hours and bailed hole clean. State draw down
test by Echometer 2951 bbls. no water.