

REPUBLIC NAT. GAS CO.
Bloomer No. 1B.

SEC. 14 T. 17 R. 11W
NE NW NW

Total Depth. 3338'
Comm. 7-25-37 Comp. 8-22-37
Contractor. Barbour & Corbett Drlg. Co.
Shot or Treated. 1000 & Reacidized 3000 Gals.
Issued. 11-6-37

County. Barton



CASING:
10" 218'
7" 3320'

Production. Pot. 1624 B.

Figures Indicate Bottom of Formations.

shale	100
sand	160
shale clay	218
shells & sand	241
shale & shells	650
anhydrite	773
shells	825
shale & shells	1125
salt	1340
lime & shale	1445
brkn lime	1510
shale	1600
lime & shells	1650
shale	1680
sand	1730
lime w/ shale brkn	1755
brkn lime	1800
lime	1880
shale	1900
brkn lime	2024
lime	2036
shale	2042
lime	2068
brkn lime	2140
lime	2160
brkn lime	2175
shale	2183
lime & shale	2259
brkn lime	2270
shale & lime shells	2340
shale	2370
lime	2400
brkn lime	2415
shale	2426
shale sticky	2436
lime hrd	2448
shale	2500
lime	2530
brkn lime	2600
lime hrd	2630
Topeka lime	2692
lime	2742
lime	2880
brkn lime	2925
lime	3006
K.C. lime	3172
lime	3316
conglomerate	3321
Top Siliceous	3321
lime	3338
Total Depth.	

Cored 3335-3338 good sat.
Fillup 2750