


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

REPUBLIC NATURAL GAS CO.
Bloomer "B" No. 4.

SEC.14 T.17 R.11 W
CSW NW

Total Depth. 3325'
Comm. 9-1-42 Comp. 9-25-42
Shot or Treated.
Contractor. Mitchell Drlg.Co.
Issued. 12-5-42

County. Barton



CASING:
8 5/8" 241' Cem. LI
5 1/2" 3297' Cem. LI

Elevation.

Production. Pot.1308 B.
287 BW

Figures Indicate Bottom of Formations.

clay, lime, shale	40
sand & lime	200
lime & shale	242
shale	300
sand	325
red bed & shells	860
anhydrite shale	933
shale & shell	1162
salt & shell	1260
salt	1345
lime, shell & shale	1445
lime, shale & sand	1626
lime & shale	1754
lime	1896
shale	1922
lime & shale brks	1967
lime	2029
lime shale	2131
lime & shale	2160
shale & shell	2255
shale & shells	2629
lime	3014
shale & lime	3079
lime	3278
lime	3310
T. D. Rotary	
lime	3325
Total Depth.	

Top Arbuckle 3297
Penetration 28'

9-21-42 1000 Gals.Acid
9-22-42 75 Bbls.Oil, No wtr
9-25-42 2500 Gals.Acid
10-16-42 1308 Bbls.Oil,
287 BW
well made 18% Wtr