


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - REPUBLIC NATURAL GAS COMPANY  
Farm - Bloomer "B" No. 6

SEC. 14 T. 17 R. 11W  
NEc NE

Total Depth. 3343'  
Comm. 10-27-47 Comp. 12-12-47  
Shot Acid, w/500 gals. 11-18-47  
Contractor. Sheffer Drilling Company  
Issued. 1-24-48

County. Barton  
KANSAS



CASING:  
10-3/4" 237' Cem. w/100 sx  
7" OD 3329' RB Cem. w/100 sx

Elevation. \_\_\_\_\_

Production. Pot. 326 BO & 6%  
water

Figures indicate Bottom of Formations.

clay & shale	0-33
gravel & clay	38
shale	143
sand	162
shale & red bed	215
shale & shells	235
clay & shells	445
red bed & shale	670
anhydrite	686
shale & shells	1430
lime & shale	1595
lime brkn	1725
lime & shale	1845
shale & pyrite or iron	1850
shale	1865
lime	1950
shale & lime	1960
rock	1969
lime & shale	1996
shale & shells	2015
lime & shale	2355
shale	2470
lime & shale	2545
shale & shells	2605
shale & lime	2918
lime hrd	2937
lime & shale	3105
lime	3124
lime & shale	3310
conglomerate	3315
conglomerate & shale	3331
Arbuckle RTD	3338
Arbuckle (Cable)	3343
Total Depth	

Cored from 3329' to 3338'  
corrected. This was 3331' to 3340'  
driller's measurements. Recovered 6'.  
Top foot shaly dolomite, bottom 5'  
dolomite ranging from dense to vugular  
porosity, also thin shale seams. Fair  
show of oil.

Tops:  
Anhydrite 670  
Arbuckle 3330 RB

Producing Formation: Arbuckle