

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - REPUBLIC NATURAL GAS CO.
Farm - Bloomer "B" No. 9

SEC. 14 T. 17 R. 11W
SW SE NE

Total Depth. 3338' Cor.
Comm. 3-14-49 Comp. 4-29-49
Shot or Treated. Acid. W/2500 gals. in 3 stages
Contractor. Pickrell Drlg. Co.
Issued. 7-2-49

County. Barton

KANSAS



CASING:
10-3/4" 304' Cem. W/125 Sx. Circ.
7" 3328' Cem. W/100 Sx.

Elevation. _____

Production. Phy. 169 BO, 4% wtr.

Figures Indicate Bottom of Formations.

surface, clay & rock	115
shale, shells, sand	305
shale & shells	450
red rock	675
lime, anhydrite	705
shale	815
shale & shells	1400
lime & shale	1780
lime	1850
lime & shale	2325
shale & shells	2480
lime & shale	2650
lime	2987
shale & lime	3021
lime & brkn lime	3301
shale & lime	3325
lime RTD	3330
lime ?	3338
Total Depth	

Tops:	
Anhydrite	675
Lansing K. C.	3035
Arbuckle	3326
Pre. Camb. RTD	3330
Penetration	12

Prod. fromation - Arbuckle

Acid. Record:
4-1-49 Acid. W/1000 gals.
4-8-49 Acid. W/ 500 gals.
4-9-49 Acid. W/1000 gals.