


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company GULF OIL CORP.
farm Olga Petermann No. 5.

SEC. 15 T. 17 R. 11 W
SW NW SE

Total Depth. 5584
Comm. 2-8-46 Comp. 3-4-46
Shot or Treated.
Contractor.
Issued. 5-11-46

County. Barton
KANSAS



CASING:
8 5/8" 257' Cem.
5 1/2" 3410' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

Salt Water
Disposal Well

surface sand, shale
& shells 0-258
shale & red bed 560
shale, red bed &
shells. 650
anhydrite 680
shale & shells w/
strks of iron 1125
salt & shale 1185
salt, shale & shells 1385
shale & lime shells 1570
shale & lime 1750
lime brkn 1840
lime & shale 2075
lime brkn 2135
shale 2215
shale & shells 2250
shale 2345
shale & lime 2675
lime 2795
lime cherty 2855
lime 3271
conglomerate, cherty 3325
Arbuckle lime 3410
lime & strks of
chert 3467
lime 3584
Total Depth

Tops:

Heebner shale 2888
Douglas shale 2914
Brown lime 2992
Lansing-K.C. 3012
Base Kans. City 3261
Perm. Basal Congl 3265
Arbuckle 3325
Pre-Cambrian 3574