


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. GULF OIL CORPORATION  
Farm. Olga Petermann No. 7

SEC. 15- T. 17 R. 11W  
SW NE SE

Total Depth. 3288  
Comm. 10-17-51 Comp. 11-11-51  
Shot or Treated.  
Contractor.  
Issued. 2-16-52

County Barton  
KANSAS



Elevation. 1871

8 5/8" 662' cem. w/325 sx Left in  
6" 3277' cem. w/100 sx " "

Production. IPP 30 bbls. oil &  
no wtr

Figures Indicate Bottom of Formations.

surface sand & shale	270
shale & shells	420
redbed	652
Anhydrite	664
shale & shells	1300
shale & lime	2255
shale	2435
shale & lime	2685
lime	2870
lime & shale	2985
lime	3280 RTD
lime	3288
Total depth	

Tops:	
Heebner	2888
Toronto	2906
Brown lime	2988
Lansing	3008
Pennsylvanian basal	
conglomerate	3272
Arbuckle	3275

Top collar on 8 5/8" csg to rotary  
bushing is 8'.

11-2-51 200 gals. acid,  
11-4-51 200 gals. acid,