

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

SHELL OIL COMPANY, INC.  
C. Giblor No. 2

SEC. 16 T. 17 R. 11 W.  
NEc SE  
330' NL 330' EL SE $\frac{1}{4}$

Total Depth. 3296 P.B. 3260  
Comm. 7-11-42 Comp. 8-2-42  
Shot or Treated 1000 gal acid.  
Contractor.  
Issued. 9-5-42

County Barton

CASING.

85/8" 351' cemented.  
4 $\frac{1}{2}$ " 3289' cemented.



Elevation.

Production. Temp. Abd.

Figures Indicate Bottom of Formations.

surface clay	75
sand and shale	150
shale and shells	1135
shale and salt	1360
shale and lime	1507
anhydrite, shale & shells	1612
broken lime	1702
lime and shale	1856
lime and shale chert strks	1915
lime and shale	2098
shale and shells	2320
shale and shells	2492
shale and lime	2655
lime	2789
lime and chert	2876
lime	3286
chert	3288
colomite	3296
Total Depth	

P.B. 3260

Top Lansing Kansas City	3020
Top of Arbuckle	3288

Good porosity 2910-25  
Dead Oil stain 3022-25  
Dead to lighter to no oil stain 3050-52  
Porosity, no stain 3110-34  
Porosity, no stain 3192-3203  
Dead Oil stain 3222-25  
Very good porosity dead oil stain 3288-91