


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas

SHELL OIL CO., INC.  
Soeken "B" No. 2.

SEC. 21 T. 17 R. 11 W  
NE NW NE  
330' f NL 986' f WL NE  $\frac{1}{4}$

Total Depth. 3559'  
Comm. 8-16-42 Comp. 12-17-42  
Shot or Treated. 12-16-42 2000 Gals. 3337-3559  
Contractor.  
Issued. 2-13-43

County. Barton



CASING:  
8 5/8" 353' Cem.

Elevation.

Production. Salt Wtr Disp.

Figures Indicate Bottom of Formations.

clay, sand, shells	125
shale & shells	355
red rock & shale	620
anhydrite	640
shale & shells	1145
shale & salt	1355
shale & shells	1480
shale & lime	1640
lime	1815
lime & shale	2609
2609 equals 2631 SLCorr.	
lime	2780
lime & chert	2844
lime, chert strks	2865
lime	3252
conglomerate & shale	
green	3277
conglomerate & chert	3288
dolomite	3315
good porosity	
dolomite	3415
quartzite	3559
Total Depth.	

Tops:  
Topeka 2636  
Lansing K.C. 2990  
Conglomerate 3252  
Arbuckle 3288  
Basal Sand 3542  
Pre-cambrian 3552