

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas


Company - VICKERS PETRO. CO., INC.
 Farm - Sockon "A" No. 5

SEC. 21 T. 17 R. 11W
 N. NE SE

Total Depth. 3270
 Comm. 8-1-50 Comp. 8-23-50
 Shot or Treated.
 Contractor.
 Issued. 10-14-50

County. Barton

KANSAS



Elevation. 1826 R.B.
 Pot.

Production. 120 BOPD / 44% wtr.

CASING:

8 5/8" 325' con. w/145 sx.
 5 1/2" 3269' con. w/100 sx.

Figures Indicate Bottom of Formations.

sand, surface & clay	250
shale & shells	325
shale, shells & sand	400
red bed	636
anhydrite	662
shale	685
shale, shells	1050
salt, shale, shells	1275
shells, lime brkn	1135
lime	1575
lime, shale & sand	1720
lime brkn	1820
lime	1940
lime, shale	2590
lime	2800
lime & shale	3268
dolo.	3270
Total Depth	

Tops:	
Heobner	2887
Brown Lansing	2995
White Lansing	3018
Arb.	3268

Cable Tools clean out to 3270 T.D.
 Fill up 1600' oil / 400' wtr. 15 hrs.
 Swabbed 4 BOPH / 1 B.PH for 4 hrs.
 Acidize w/500 gal. Put on pnp.