

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock,
 Wichita, Kansas

Company- SHELL OIL COMPANY
 Farm- H₄ Disque No. 6

SEC. 22 T. 17 R. 11W
 SW NW NE
 991' NL & 330' WL of NE/4

Total Depth. 3334; PB 3295
 Comm. 1-15-52 Comp. 2-3-52
 Shot or Treated.
 Contractor. B & R & Signal Oilfield Service
 Issued. 4-19-52

County Barton
 KANSAS



CASING:

Elevation. 1839 DF

10 3/4" 380' cem. w/375 sx
 7" 3333' cem. w/200 sx

Production. Drawdown Pot. 752
 (Figures indicate Bottom of Formations. bbls. oil & 666 bbls. wtr)

cellar	9
surface clay	50
clay & shells	125
shale & shells	295
shale & sand strks	345
shale	426
sand & redbed	650
Anhydrite	690
redbed	810
shale & shells	1240
salt & shale	1345
lime & shale	1770
lime	1950
lime & shale	2000
shale	2178
lime	2188
shale	2210
lime	2264
shale	2340
lime	2356
shale	2410
lime	2468
shale	2554
lime	2605
shale & lime	2639
lime	2698
shale	2705
lime	2722
shale	2726
lime	2748
shale	2760
lime	2785
shale	2789
lime	2838
shale	2850
lime	2885
shale	2890
lime	2919
shale, gray, red & black	2985
lime	2999
shale	3004
lime	3111
shale gray	3115
lime	3204
gray & red shale	3213
lime	3240
gray & red shale	3246
lime	3261
green shale	3266
dolomite	3334

Schlumberger Tops:

Topeka	2632
Heebner	2883
Toronto	2884
Brown lime	2985
Lansing-Kansas City	3004
Arbuckle	3266

SL correction 3092 = 3086

Ran Sch., laterolog, Microlog,
 and Gamma Ray log

Perf. 326603272 w/24 M-2 Jets

4/ft. wire line T.D. 3295

Az w/500 gals. max. press. 325 PSI
 tubing 450 psi casing.

Rotary Total depth; PB 3295