

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- SHELL OIL CO.  
Farm-H. Disque No. 7

SEC. 22 T. 17 R.11W  
SW SW NE  
330' BL 330' WL NE/4

CORRECTED LOG

Total Depth. 3332 P.B. 3282  
Comm. 3-24-52 Comp. 4-30-52  
Shot or Tracked.  
Contractor.  
Issued. 7-26-52

County Barton  
KANSAS



CASING:  
10 3/4" 350'  
7" 3331'

Elevation. 1839  
Phys. State Pot.  
Production. 28 bbls & 128 BW

Figures Indicate Bottom of Formations.

shale	380	Az/ 250 gals. 3265-3272; 3265-
shale, shells, pyrite	1255	3274; 3256-3274; 500 gals. 3256-74.
lime & shale	2095	
shale w/strks of lime	2155	
lime & shale	2158	
shale & lime strks	2215	
lime w/strks of shale	2270	
shale	2334	
lime	2355	
shale	2400	
lime w/strks of shale	2455	
shale & lime	2478	
lime	2488	
shale	2550	
lime & strks of shale	2600	
shale & lime	2634	
shale	2642	
lime	2703	
shale & lime	2713	
lime	2731	
shale drk gry	2740	
lime	2745	
shale	2752	
lime	2785	
shale	2790	
lime	2800	
lime & blk shale	2812	
lime	2884	
shale blk	2887	
lime	2894	
shale & shaley lime	2901	
lime	2918	
red, green, blk & gry		
shale	2986	
lime	2997	
shale	3004	
lime	3032	
shale	3036	
lime	3068	
shale, lime strks	3082	
lime	3098	
shale	3100	
lime	3112	
shale	3116	
lime	3134	
shale, strks of lime	3148	
lime	3206	
shale	3215	
lime	3248	
shale & lime	3256	
lime	3263	
green shale	3267	
dolo.	3332	
Total Depth P.B.	3282	

Tops: Sample	
Topeka	2642
Heebner	2884
Toronto	2901
Brown lime	2986
Lansing-K.C.	3004
Arbuckle	3267