


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL COMPANY  
Farm Anna Heller No. 5

SEC. 22 T. 17 R. 11W  
CW/2 SW SE  
660' fSL & 330' fWI SE/4

Total Depth. 3295'  
Comm. 12-11-46 Comp. 12-29-46  
Shot or Treated. Acid.  
Contractor. Claude Wentworth Co.  
Issued. 3-29-47

County. Barton  
KANSAS



CASING:

8-5/8" OD 406' Cem. w/200 sx  
5-1/2" 3276 1/2" Cem. w/125 sx

Elevation. \_\_\_\_\_

Production. 319 BO

Figures Indicate Bottom of Formations.

surface soil & clay	0-90	12-29-46 - Acidized w/500 gals. 3276 1/2-95'.
sand	120	12-30-46 - Acidized w/1500 gals. 3276 1/2-95'
shale	376	
shale & shells	435	
red bed	670	3146-56' Per. sli. sat.
anhydrite	710	3276-80' Med. por., good sat.
shale	1020	3280-81' Sli. por. & sat.
salt	1110	3281-86' Spotted Por. & sat.
shale	1300	670' OIH in 12 hrs.
salt	1455	3286-91' Strks fair por. & sat.
lime brkn	1550	3291-95' No por. or sat. 1200' OIH
lime	1660	
shale w lime	1705	
lime	1740	
shale	1875	
lime	1955	
lime brkn	2040	
shale	2225	
limey shale	2420	
lime brkn	2480	
shale	2605	
shale w lime	2695	
shale	2710	
lime brkn	2800	
lime	2912	
lime & shale	3018	
lime	3182	
(3146-56' gy & brwn oolitic lime, por. sli. sat.)		
shale	3230	
lime	3274	
chert gy & sdy		
lime	3276	
dolomite gy & brwn xlyn, med por. & good sat.	3280	
dolomite brwn & gy, sli. por. & sat.	3281	
(bailed & tested 1 hr. 1/2 BO, no wtr.)		
dolomite brwn & gy, spotted por. & sat. (670' OIH in 12 hrs.)	3286	
dolomite dense gy streaks of fair por. & sat.	3291	
dolomite dense gy no por. or sat. (1200' OIH)	3295	
Total Depth.		
Tops:		
Lansing Lime	3008	
Arbuckle lime	3276	