


STANOLIND OIL AND GAS CO.
Onno Soeken No. 2

SEC. 22 T. 17 R. 11 W
SE NW NW
1650' N SL 990' E WL NW $\frac{1}{4}$

Total Depth. 3298
Comm. 12-21-41 Comp. 1-6-42
Shot or Treated
Contractor.
Issued 2-14-42

County Barton.



CASING.

85/8" 350' cemented.
5 1/2" 3289' 11 cemented.

Elevation
D.D.I.C.
Production. Pot. 4247 B.
no wtr. Nat.

Figures Indicate Bottom of Formations.

clay	20
sgale	50
sand	60
shale and shells	100
sand	220
shale and shells	360
shale	420
red bed	485
shale and red beds	650
anhydrite	682
shale & red bed	875
shale and shells	1105
salt	1240
shale and shells	1440
lime	2015
shale and shale	2160
lime and shale	2320
lime	2390
lime and shale	2580
broken lime	2720
lime	2900
shale and lime	3015
lime	3270
chert and lime	3292
Arbuckle Dolomite	3298

Total Depth.

Top Lansing 3016
Arbuckle Dolomite 3292-3298

Swabbed 25,30,28, BOPH Nat. 3 Hr test 1000' from top.
D.D. I.C. 4247 BOPD No wtr. Nat.