


STANOLIND OIL & GAS CO.  
Onno Soeken No. 3.

SEC. 22 T. 17 R. 11 W.  
CN $\frac{1}{2}$  SW NW  
990' N SL 660' E WL NW $\frac{1}{4}$

Total Depth. 3289  
Comm. 4-14-42 Comp. 4-30-42  
Shot or Treated.  
Contractor.  
Issued. 6-6-42

County Barton.



Rotary and Cable.

CASING.

85/8" 356'3" Cem.  
5 $\frac{1}{2}$ " 3281'9" Cem.

Elevation.

Drawdown  
Production Pot. 3000 B.  
Ind. Cap. 21,038 B.

Figures Indicate Bottom of Formations.

cellar	4
shale	125
shale and shells	648
anhydrite	670
shale and shells	1095
salt	1200
shale and shells	1520
lime and shale	1695
broken lime	1725
sand	1733
broken lime	1865
shale and shells	2560
lime	2945
lime and shale	3045
lime	3284 $\frac{1}{2}$
Arbuckle Dolomite	3289
Total Depth.	

Tops; Lansing 3010  
Arbuckle 3284 $\frac{1}{2}$ -89 SLM  
3282 $\frac{1}{2}$ -87 (OT)

Initial Swab test 850' from  
top - 36 BOPH