

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- SKELLY OIL COMPANY

Farm- Adam Disque

No. 6

SEC. 9 T. 17 R. 11W

NW SE NW

990' from EL, 990' from SL, NE $\frac{1}{4}$

Total Depth. 3344

Comm. 8-26-51

Comp. 9-8-51

Shot or Treated.

Contractor. Claude Wentworth Drlg, Inc.

Issued. 10-27-51

County Barton

KANSAS



CASING:

8 5/8" 705' cem w/300 sx.

Elevation. 1860 DF

Production. dry

Figures Indicate Bottom of Formations.

surface soil, daly	40
clay, gravel	95
shale, shells	520
red bed	695
anhydrite	705
Drilled 12 1/4" hole	
anhydrite	720
red bed, shale, shells	950
shale, salt	1075
shale, shells	1105
lime brkn, shale	1190
shale, lime	1685
sand, lime	1710
shale, lime	2010
lime brkn, shale	2100
lime, shale	2150
shale, shells	2265
shale	2345
shale, lime	2480
shale, shells	2560
shale	2600
shale, lime	2730
lime	2920
shale, shells	3005
shale	3015
lime	3095
lime, shale	3145
lime	3204
lime finely xyn	3211
Fair porosity and	
stain, live oil in	
samples w/good odor	
3204-3211	
lime	3270
shale, lime	3293
conglomerate	3340
dolo. light gray	3344
Total Depth	

Tops:

Anhydrite	695
Heebner Shale	2914
Toronto Lime	2929
Douglas	2945
Brown Lime	3013
Lansing Lime	3030
Conglomerate	3293
Arbuckle Lime	3340

Slight porosity, no stain
3340-44.Ran halliburton DST, packer
set @ 3203', open 1 1/2 hrs.,
rec. 10' of drilling mud, no
BHP