


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - ROBERT L. WILLIAMS  
Farm - George Ehly No. 1

SEC. 1 T. 17 R. 11W  
SE NW SE

Total Depth. 3178  
Comm. 3-14-50 Comp. 3-21-50  
Shot or Treated.  
Contractor. HARMS & KNIGHT DRILLING CO.  
Issued. 4-29-50

County. Barton  
KANSAS



CASING:  
8 5/8" 245' cem w/160 sx  
5 1/2" 3174' cem w/125 sx

Elevation. \_\_\_\_\_

Production. 303 Bbls.

Figures Indicate Bottom of Formations.

shale, sand	185
shale, shells	246
shale shells, redbed	350
sand, red bed	650
shale, shells, red bed	725
red bed	733
anhydrite	762
red bed, shells	1040
shale, shells	1200
salt, shale	1390
shale shells	1670
shale, lime	2245
shale	2485
broken lime, sand	2625
shale, lime	3150
lime	3178
Total Depth	

Tops:

Heebner Shale	2980
Brown Lime	3082
Lansing	3101

All measurements are taken from rotary bushing.

At 3105 feet, 4' in the Lansing samples were circulated, and showed good porosity with slight staining.

At 3178 samples were circulated which showed good porosity in fossiliferous lime, and had good even staining and a good odor.

A D.S.T. from 3171-78 had a strong blow of air immediately; showed gas in 12 minutes, and recovered 185' of clean light oil in 30 mins. The shut in bottom hole pressure was 610# in 10 minutes and the final flow pressure was 90#.