

TRANSWESTERN OIL CO.
Fee No. 2. (Krautwurst)

SEC. 12 T. 17 R. 11W
Sec SE

Total Depth. 3231'
Comm. 1-27-38 Comp. 3-5-38
Shot or Treated. 2000 Gals., 77 shots 3099-
Contractor. Patton Drlg.Co. 3106
Issued, 5-7-38

County. Barton



CASING:

20" 221'P
15 1/2" 399'P
13 3/8" 625'P
10" 2206'P
8 1/4" 3229 1/2'

Elevation.

Production. Pot. 960 B.

Figures Indicate Bottom of Formations.

cellar	14	shale blue	1820	lime	2625
post rock	28	lime	1825	shale	2642
clay yellow	30	shale blue	1830	lime	2730
shale blue	95	red rock	1838	shale	2735
shale lgt	110	lime	1855	lime	2750
sand	115	shale	1865	shale	2760
shale lgt	120	red rock	1870	lime	2830
sand	155	lime	1890	sdv lime	2870
red rock	160	red rock	1895	lime hrd	2889
sdv & yellow clay	195	lime	1925	shale	2892
shale blue	220	shale red & blue	1931	lime	2900
sdv shale	225	lime	1943	shale	2908
shale blue	233	shale red	1947	lime	2920
red rock	260	lime	2000	shale brown	2945
shale sdv grey	295	shale grey	2010	lime	2948
shale blue	365	lime	2022	shale blue	2993
sand	370	shale blue	2040	lime	2998
shale blue	396	lime	2045	shale	3010
sand HPW	410	shale red	2050	K.C. lime	3036
lime & iron	412	lime	2120	shale	3038
shale blue	455	shale	2125	lime	3068
red rock	630	lime	2135	shale	3075
anhydrite limo	668	shale blue	2145	lime hrd	3100
red rock	890	lime	2155	lime sft oil pay	3105
shale blue	945	shale	2187	lime	3106
shale red	985	wtr sand	2192	shale white	3107
shale	1075	lime	2198	lime hrd	3117
salt	1330	shale	2201	lime sft wtr	3126
shale blue	1355	lime	2204	lime	3155
limo	1360	shale	2210	shale	3157
shale blue	1365	lime	2214	lime hrd	3189
limo	1375	shale	2230	lime sft oil	3192
shale blue	1380	lime	2245	lime sft	3200
limo	1400	shale	2255	lime hrd	3224
shale	1406	lime	2260	shale	3227
lime	1420	shale	2270	lime hrd	3230
shale	1425	lime	2280	lime sft	3231
lime	1430	shale	2340	Total Depth.	
shale	1435	lime	2360		
lime	1460	shale	2365		
shale red	1465	lime	2370	Prod. Formation:	
red rock	1475	shale	2405	K.C. lime 3099-3106	
brkn limo	1495	lime	2430		
lime hrd	1520	shale	2435		
shale grey	1540	lime	2445		
lime	1573	shale	2450		
shale red	1590	lime brkn	2475		
lime	1620	shale	2485		
shale	1625	lime	2500		
lime	1630	shale	2510		
shale	1640	lime	2514		
lime	1660	shale	2532		
shale	1665	lime	2545		
lime	1715	shale	2560		
sdv lime sft	1725	lime	2565		
lime hrd	1775	shale	2570		
shale	1785	lime	2585		
lime	1790	shale	2595		
shale red	1794	lime	2610		
lime hrd	1810	shale	2615		