

October, 1939.

✓
Weaver #1 Stumps,
NE NE NE, 3-17S-12W,
Elevation 1883' _{h. >} P

Pennsylvanian conglomerate. 3345-~~3362~~'-3355'
3345-3352 Sandy lime grading downwards into medium to
coarse sand.
3352-3355 Conglomerate of sand and stained chert.

Arbuckle residuum. 3355-3362'
3355-3360 Clay, red, with included sand.
3360-3362 Clay, red, mixed with chert.

Arbuckle. Top, 3362' Penetration 21' Sub-sea, minus 1479'.
3362-3383 Dolomite, white, medium crystalline at top and
coarsely crystalline at base.

Top Pre-Cotter estimated to have been 3349', restored,
or -1466'.

JOHN W. COOKMAN